

10/530114

PCT/CH 03/00231
Rec'd PCT/PTO 01 APR 2005

SCHWEIZERISCHE EIDGENOSSENSCHAFT
CONFÉDÉRATION SUISSE
SWISS CONFEDERATION

REC'D 15 APR 2003	
WIPO	PCT

Bescheinigung

Die beiliegenden Akten stimmen überein mit den ursprünglichen Unterlagen der auf den nächsten Seiten bezeichneten, beim unterzeichneten Amt als Anmeldeamt im Sinne von Art. 10 des Vertrages über die internationale Zusammenarbeit auf dem Gebiet des Patentwesens (PCT) eingegangenen Patentanmeldung.

Attestation

Les documents ci-joints sont conformes aux pièces originales relative à la demande de brevet spécifiée aux pages suivantes, déposées auprès de l'Office soussigné, en tant qu'Office récepteur au sens de l'article 10 du Traité de coopération en matière de brevets (PCT).

Confirmation

It is hereby confirmed that the attached documents are corresponding with the original pages of the international application, as identified on the following pages, filed under Article 10 of the Patent Cooperation Treaty (PCT) at the receiving office named below.

**PRIORITY
DOCUMENT**

SUBMITTED OR TRANSMITTED IN
COMPLIANCE WITH RULE 17.1(a) OR (b)

Bern, 10. April 2003

Eidgenössisches Institut für Geistiges Eigentum
Institut Fédéral de la Propriété Intellectuelle
Swiss Federal Intellectual Property Institute

Patentverfahren
Administration des brevets
Patent Administration

Rolf Hofstetter
Rolf Hofstetter

BEST AVAILABLE COPY

PCT

REQUEST

The undersigned requests that the present international application be processed according to the Patent Cooperation Treaty.

For Receiving Office use only	
PCT/CH 02 / 00545	
International Application No.	
01. Okt. 2002 (01. 10. 02)	
International Filing Date	
RO/CH - Internationale Anmeldung PCT	
Name of receiving Office and "PCT International Application"	
Applicant's or agent's file reference (if desired) (12 characters maximum) RS/sk-15807	

Box No. I	TITLE OF INVENTION	
	Coil form	
Box No. II	APPLICANT <input type="checkbox"/> This person is also inventor	
Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)		Telephone No.
Ascom Energy Systems AG Belpstrasse 37 3000 Bern 14 Schweiz *		Facsimile No.
		Teleprinter No.
		Applicant's registration No. with the Office
State (that is, country) of nationality: Switzerland		State (that is, country) of residence: Switzerland
This person is applicant for the purposes of: <input type="checkbox"/> all designated States <input checked="" type="checkbox"/> all designated States except the United States of America <input type="checkbox"/> the United States of America only <input type="checkbox"/> the States indicated in the Supplemental Box		
Box No. III	FURTHER APPLICANT(S) AND/OR (FURTHER) INVENTOR(S)	
Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country. The country of the address indicated in this Box is the applicant's State (that is, country) of residence if no State of residence is indicated below.)		This person is:
PILNIAK Jürgen Udenstrasse 11 59581 Warstein/Allagen Deutschland *		<input type="checkbox"/> applicant only
		<input checked="" type="checkbox"/> applicant and inventor
		<input type="checkbox"/> inventor only (If this check-box is marked, do not fill in below.)
		Applicant's registration No. with the Office
State (that is, country) of nationality: Germany		State (that is, country) of residence: Germany
This person is applicant for the purposes of: <input type="checkbox"/> all designated States <input type="checkbox"/> all designated States except the United States of America <input checked="" type="checkbox"/> the United States of America only <input type="checkbox"/> the States indicated in the Supplemental Box		
<input type="checkbox"/> Further applicants and/or (further) inventors are indicated on a continuation sheet.		
Box No. IV	AGENT OR COMMON REPRESENTATIVE; OR ADDRESS FOR CORRESPONDENCE	
The person identified below is hereby/has been appointed to act on behalf of the applicant(s) before the competent International Authorities as: <input checked="" type="checkbox"/> agent <input type="checkbox"/> common representative		
Name and address: (Family name followed by given name; for a legal entity, full official designation. The address must include postal code and name of country.)		Telephone No.
ROSHARDT Werner A., JUNGHANS Jürgen, STEINER Anton, STÄBLER Roman Keller & Partner Patentanwälte AG Schmiedenplatz 5, Postfach CH-3000 Bern		+41 31 310 80 80
		Facsimile No.
		+41 31 310 80 70
		Teleprinter No.
		Agent's registration No. with the Office
<input type="checkbox"/> Address for correspondence: Mark this check-box where no agent or common representative is/has been appointed and the space above is used instead to indicate a special address to which correspondence should be sent.		

Box No. V DESIGNATION OF STATES

Mark the applicable check-boxes below; at least one must be marked.

The following designations are hereby made under Rule 4.9(a):

Regional Patent

- ☐ AP ARIPO Patent: GH Ghana, GM Gambia, KE Kenya, LS Lesotho, MW Malawi, MZ Mozambique, SD Sudan, SL Sierra Leone, SZ Swaziland, TZ United Republic of Tanzania, UG Uganda, ZM Zambia, ZW Zimbabwe, and any other State which is a Contracting State of the Harare Protocol and of the PCT (if other kind of protection or treatment desired, specify on dotted line)
- ☐ EA Eurasian Patent: AM Armenia, AZ Azerbaijan, BY Belarus, KG Kyrgyzstan, KZ Kazakhstan, MD Republic of Moldova, RU Russian Federation, TJ Tajikistan, TM Turkmenistan, and any other State which is a Contracting State of the Eurasian Patent Convention and of the PCT
- ☒ EP European Patent: AT Austria, BE Belgium, BG Bulgaria, CH & LI Switzerland and Liechtenstein, CY Cyprus, CZ Czech Republic, DE Germany, DK Denmark, EE Estonia, ES Spain, FI Finland, FR France, GB United Kingdom, GR Greece, IE Ireland, IT Italy, LU Luxembourg, MC Monaco, NL Netherlands, PT Portugal, SE Sweden, SK Slovakia, TR Turkey, and any other State which is a Contracting State of the European Patent Convention and of the PCT
- ☐ OA OAPI Patent: BF Burkina Faso, BJ Benin, CF Central African Republic, CG Congo, CI Côte d'Ivoire, CM Cameroon, GA Gabon, GN Guinea, GQ Equatorial Guinea, GW Guinea-Bissau, ML Mali, MR Mauritania, NE Niger, SN Senegal, TD Chad, TG Togo, and any other State which is a member State of OAPI and a Contracting State of the PCT (if other kind of protection or treatment desired, specify on dotted line)

National Patent (if other kind of protection or treatment desired, specify on dotted line):

- | | | |
|--|---|---|
| <input type="checkbox"/> AE United Arab Emirates | <input type="checkbox"/> GM Gambia | <input type="checkbox"/> NZ New Zealand |
| <input type="checkbox"/> AG Antigua and Barbuda | <input type="checkbox"/> HR Croatia | <input type="checkbox"/> OM Oman |
| <input type="checkbox"/> AL Albania | <input type="checkbox"/> HU Hungary | <input type="checkbox"/> PH Philippines |
| <input type="checkbox"/> AM Armenia | <input type="checkbox"/> ID Indonesia | <input type="checkbox"/> PL Poland |
| <input type="checkbox"/> AT Austria | <input type="checkbox"/> IL Israel | <input type="checkbox"/> PT Portugal |
| <input type="checkbox"/> AU Australia | <input type="checkbox"/> IN India | <input type="checkbox"/> RO Romania |
| <input type="checkbox"/> AZ Azerbaijan | <input type="checkbox"/> IS Iceland | <input type="checkbox"/> RU Russian Federation |
| <input type="checkbox"/> BA Bosnia and Herzegovina | <input type="checkbox"/> JP Japan | |
| <input type="checkbox"/> BB Barbados | <input type="checkbox"/> KE Kenya | <input type="checkbox"/> SD Sudan |
| <input type="checkbox"/> BG Bulgaria | <input type="checkbox"/> KG Kyrgyzstan | <input type="checkbox"/> SE Sweden |
| <input type="checkbox"/> BR Brazil | <input type="checkbox"/> KP Democratic People's Republic of Korea | <input type="checkbox"/> SG Singapore |
| <input type="checkbox"/> BY Belarus | <input type="checkbox"/> KR Republic of Korea | <input type="checkbox"/> SI Slovenia |
| <input type="checkbox"/> BZ Belize | <input type="checkbox"/> KZ Kazakhstan | <input type="checkbox"/> SK Slovakia |
| <input type="checkbox"/> CA Canada | <input type="checkbox"/> LC Saint Lucia | <input type="checkbox"/> SL Sierra Leone |
| <input type="checkbox"/> CH & LI Switzerland and Liechtenstein | <input type="checkbox"/> LK Sri Lanka | <input type="checkbox"/> TJ Tajikistan |
| <input type="checkbox"/> CN China | <input type="checkbox"/> LR Liberia | <input type="checkbox"/> TM Turkmenistan |
| <input type="checkbox"/> CO Colombia | <input type="checkbox"/> LS Lesotho | <input type="checkbox"/> TN Tunisia |
| <input type="checkbox"/> CR Costa Rica | <input type="checkbox"/> LT Lithuania | <input type="checkbox"/> TR Turkey |
| <input type="checkbox"/> CU Cuba | <input type="checkbox"/> LU Luxembourg | <input type="checkbox"/> TT Trinidad and Tobago |
| <input type="checkbox"/> CZ Czech Republic | <input type="checkbox"/> LV Latvia | |
| <input type="checkbox"/> DE Germany | <input type="checkbox"/> MA Morocco | <input type="checkbox"/> TZ United Republic of Tanzania |
| <input type="checkbox"/> DK Denmark | <input type="checkbox"/> MD Republic of Moldova | <input type="checkbox"/> UA Ukraine |
| <input type="checkbox"/> DM Dominica | <input type="checkbox"/> MG Madagascar | <input checked="" type="checkbox"/> US United States of America |
| <input type="checkbox"/> DZ Algeria | <input type="checkbox"/> MK The former Yugoslav Republic of Macedonia | <input type="checkbox"/> UZ Uzbekistan |
| <input type="checkbox"/> EC Ecuador | <input type="checkbox"/> MN Mongolia | <input type="checkbox"/> VN Viet Nam |
| <input type="checkbox"/> EE Estonia | <input type="checkbox"/> MW Malawi | <input type="checkbox"/> YU Yugoslavia |
| <input type="checkbox"/> ES Spain | <input type="checkbox"/> MX Mexico | <input type="checkbox"/> ZA South Africa |
| <input type="checkbox"/> FI Finland | <input type="checkbox"/> MZ Mozambique | <input type="checkbox"/> ZM Zambia |
| <input type="checkbox"/> GB United Kingdom | <input type="checkbox"/> NO Norway | <input type="checkbox"/> ZW Zimbabwe |
| <input type="checkbox"/> GD Grenada | | |
| <input type="checkbox"/> GE Georgia | | |
| <input type="checkbox"/> GH Ghana | | |

Check-boxes below reserved for designating States which have become party to the PCT after issuance of this sheet:

- | | | |
|--------------------------------|--------------------------------|--------------------------------|
| <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |
| <input type="checkbox"/> | <input type="checkbox"/> | <input type="checkbox"/> |

Precautionary Designation Statement: In addition to the designations made above, the applicant also makes under Rule 4.9(b) all other designations which would be permitted under the PCT except any designation(s) indicated in the Supplemental Box as being excluded from the scope of this statement. The applicant declares that those additional designations are subject to confirmation and that any designation which is not confirmed before the expiration of 15 months from the priority date is to be regarded as withdrawn by the applicant at the expiration of that time limit. (Confirmation (including fees) must reach the receiving Office within the 15-month time limit.)

Box No. VI PRIORITY CLAIM

The priority of the following earlier application(s) is hereby claimed:

Filing date of earlier application (day/month/year)	Number of earlier application	Where earlier application is:		
		national application: country or Member of WTO	regional application:* regional Office	international application: receiving Office
item (1)				
item (2)				
item (3)				
item (4)				
item (5)				

☐ Further priority claims are indicated in the Supplemental Box.

The receiving Office is requested to prepare and transmit to the International Bureau a certified copy of the earlier application(s) (only if the earlier application was filed with the Office which for the purposes of this international application is the receiving Office) identified above as:

☐ all items ☐ item (1) ☐ item (2) ☐ item (3) ☐ item (4) ☐ item (5) ☐ other, see Supplemental Box

* Where the earlier application is an ARIPO application, indicate at least one country party to the Paris Convention for the Protection of Industrial Property or one Member of the World Trade Organization for which that earlier application was filed (Rule 4.10(b)(ii)):

Box No. VII INTERNATIONAL SEARCHING AUTHORITY

Choice of International Searching Authority (ISA) (if two or more International Searching Authorities are competent to carry out the international search, indicate the Authority chosen; the two-letter code may be used):

ISA / EPO

Request to use results of earlier search; reference to that search (if an earlier search has been carried out by or requested from the International Searching Authority):

Date (day/month/year) Number Country (or regional Office)

Box No. VIII DECLARATIONS

The following declarations are contained in Boxes Nos. VIII (i) to (v) (mark the applicable check-boxes below and indicate in the right column the number of each type of declaration):

Number of
declarations

- | | | |
|---|--|---|
| <input type="checkbox"/> Box No. VIII (i) | Declaration as to the identity of the inventor | : |
| <input type="checkbox"/> Box No. VIII (ii) | Declaration as to the applicant's entitlement, as at the international filing date, to apply for and be granted a patent | : |
| <input type="checkbox"/> Box No. VIII (iii) | Declaration as to the applicant's entitlement, as at the international filing date, to claim the priority of the earlier application | : |
| <input type="checkbox"/> Box No. VIII (iv) | Declaration of inventorship (only for the purposes of the designation of the United States of America) | : |
| <input type="checkbox"/> Box No. VIII (v) | Declaration as to non-prejudicial disclosures or exceptions to lack of novelty | : |

Box No. IX CHECK LIST; LANGUAGE OF FILING

This international application contains:

(a) the following number of sheets in paper form:

request (including declaration sheets) : 4
 description (excluding sequence listing part) : 12
 claims : 3
 abstract : 1
 drawings : 3

Sub-total number of sheets : 23

sequence listing part of description (actual number of sheets if filed in paper form, whether or not also filed in computer readable form; see (b) below) :

Total number of sheets : 23

(b) sequence listing part of description filed in computer readable form

(i) ☐ only (under Section 801(a)(i))(ii) ☐ in addition to being filed in paper form (under Section 801(a)(ii))

Type and number of carriers (diskette, CD-ROM, CD-R or other) on which the sequence listing part is contained (additional copies to be indicated under item 9(ii), in right column):

This international application is accompanied by the following item(s) (mark the applicable check-boxes below and indicate in right column the number of each item):

1. ☒ fee calculation sheet : 1
 2. ☐ original separate power of attorney : follows
 3. ☐ original general power of attorney :
 4. ☐ copy of general power of attorney; reference number, if any: :
 5. ☐ statement explaining lack of signature :
 6. ☐ priority document(s) identified in Box No. VI as item(s): :
 7. ☐ translation of international application into (language): :
 8. ☐ separate indications concerning deposited microorganism or other biological material :
 9. ☐ sequence listing in computer readable form (indicate also type and number of carriers (diskette, CD-ROM, CD-R or other))
 (i) ☐ copy submitted for the purposes of international search under Rule 13ter only (and not as part of the international application) :
 (ii) ☐ (only where check-box (b)(i) or (b)(ii) is marked in left column) additional copies including, where applicable, the copy for the purposes of international search under Rule 13ter :
 (iii) ☐ together with relevant statement as to the identity of the copy or copies with the sequence listing part mentioned in left column :
 10. ☐ other (specify): :

Figure of the drawings which should accompany the abstract: fig. 2

Language of filing of the international application: English

Box No. X SIGNATURE OF APPLICANT, AGENT OR COMMON REPRESENTATIVE

Next to each signature, indicate the name of the person signing and the capacity in which the person signs (if such capacity is not obvious from reading the request).

Berne, 1 October 2002

Keller & Partner
 Patentanwälte AG
 Werner A. Roshardt, Patent Attorney

For receiving Office use only

1. Date of actual receipt of the purported international application:	0 1. Okt. 2002 (0 1. 10. 02)	2. Drawings: <input type="checkbox"/> received: <input type="checkbox"/> not received:
3. Corrected date of actual receipt due to later but timely received papers or drawings completing the purported international application:		
4. Date of timely receipt of the required corrections under PCT Article 11(2):		
5. International Searching Authority (if two or more are competent): ISA /	6. <input type="checkbox"/> Transmittal of search copy delayed until search fee is paid	

For International Bureau use only

Date of receipt of the record copy by the International Bureau:

Coil form

Technical field

The invention relates to a coil form for forming an inductive element with a core and at least one coil, the coil form including a hollow coil body for insertion of the core, the coil
5 body having an outer surface for holding the at least one coil and the coil form further including at least one separating plate which surrounds the outer surface of the coil body thereby dividing the surface into at least one coil area. The invention further relates to an inductive element with such a coil form and a coil form having a hollow coil body for insertion of a core of an inductive element and having an outer surface for holding a coil of the
10 inductive element.

Prior art

In the manufacturing of electric and/or electronic components exists an ongoing demand for smaller components while their power density should be increased at the same time. This is particularly true in the manufacturing of inductive elements such as transformers, inductors or chokes. One of the major problems when reducing the size of inductive elements is to dissipate the heat, which is generated within the magnetic circuit, efficiently.

Document EP 0 133 661 shows a transformer type, which is widely known in the art, either in the formation shown or in different variations. Each winding of the transformer is wound on a separate coil body which comprises a flange on each end to hold the windings in the correct position. When the transformer is fitted together, a thin metal foil is inserted between two adjacent coil bodies to provide for electrical isolation as well as for shielding.

Since this transformer does not include an efficient cooling of the circuit, it is not suited for high power applications and its leakage inductance is quite bad.

Another transformer is described in the publication FR 2 476 898. The transformer comprises a magnetic core with three legs where all of the windings of the transformer are formed by a plurality of flat coils. As the coils are positioned directly one after another, they are electrically isolated all of their surface. The coils generally have a rectangular shape, include an air gap and are provided directly around the middle core leg.

This transformer too does not provide for an efficient cooling. The flat coils are electrically isolated which prevents an efficient heat dissipation. Furthermore, this type of transformer can not be used in applications, where at least one of the transformer windings shall be realised with isolated copper wires.

In order to provide transformers that require only a small space, planar transformers where the windings are formed by copper traces that are etched on a printed circuit board, have been introduced. Furthermore, different cooling methods are known to enhance heat

dissipation. However, while planar transformers are suited very well in certain applications, they are not useful in other applications.

Summary of the invention

5 It is therefore an object of the invention to provide a coil form of the kind initially mentioned, particularly to provide a coil form for forming of a small transformer with enhanced heat dissipation capabilities.

10 The object of the invention is achieved by the coil form defined in claim 1. The coil form according to the invention is designed to form an inductive element with a magnetic core and at least one coil. The coil form includes a hollow coil body for insertion of the core and an outer surface for holding the coils. The coil form further includes at least one separating plate which surrounds the outer surface of the coil body and thereby divides the surface into at least one coil area. While the coil body is made of plastic, the separating plate is made of metal and has an opening for pushing the separating plate over the coil body. The separating plate further has a slit which prohibits leakage currents within the separating plate.

15 Fabricating the separating plate from metal results in several advantages of the invention. First of all, the metallic plate helps to dissipate the heat which is generated either within the plate or within the coils which are positioned directly adjacent to the plate. Efficient cooling of the inductive element can be achieved. Another advantage is that the separating plate serves as a side support for the coils that are provided within the coil area or coil areas. Furthermore, the metallic plates have a positive effect on the leakage inductances and the overall stability of the coil form.

20 While many different shapes of the coil body are possible, for example a coil body that has an overall cylindrical shape, the coil body preferably includes two portions, a coil portion and a flange portion on an end region of the coil portion. The coil portion is of the kind of a hollow cylinder on the surface of which the coils of the inductive element are provided. The

25

core of the inductive element is insertable into the coil portion. On its outer surface, the coil portion includes at least one recess for positioning and holding the separating plate in the correct position.

5 The coils of the inductive element, which are provided on the surface of the coil body, have to be connected to a corresponding electrical circuit. The ends of the coils could be connected directly to another component of the electrical circuit or to a corresponding contact bank where the electrical circuit is connected to as well.

10 In an advantageous embodiment of the invention, the flange portion includes a plurality of terminals where at least an end of the at least one coil is electrically conductively connectable to one on the terminals. The size, shape and arrangement of the terminals can be such that they can be connected directly to corresponding taps or connectors of a printed circuit board or the like.

15 The separating plate, either its outline or the outline of its opening, can be of any shape. However, it is advantageous to choose the shape of the opening of the separating plate such that it substantially corresponds to the shape of the outer surface of the coil portion of the coil body. The shape of the separating plate is chosen such that an internal diameter of the separating plate (the diameter of the opening) is smaller than a corresponding outer diameter of the coil body. This means that the opening of the separating plate is smaller than the coil body.

20 Therefore, either the coil body or the separating plate have to be deformed to push the separating plate in its correct position. In order to deform the separating plate, which is made of metal, it would have to be made very thin, which would cause unwanted instabilities of the coil form. It is more useful to build the coil body such that it is deformable. This can be either achieved by using a flexible plastic or it can be achieved by a divided coil
25 body which comprises at least two elements. The elements are formed such that they include means to fit them together to form the coil body. Hence, the coil body can be pressed together in order to push the separating plate in its correct position on the outside of the coil body.

While the divided coil body can comprise three or more elements, it is sufficient that it comprises only two elements. While any kind of positive or non-positive locking is suited to connect the elements, it is preferred that the means to fit the two elements together include a recess on the first element and a corresponding projection on the second element.

- 5 There are many ways to divide the coil body into two elements. One can for example think of almost any plane which intersects the coil body to divide it into two elements. However, as the coil portion of the coil body according to the invention is preferably built of the kind of a right cylinder where the base planes are perpendicular to the outer surface of the coil portion, the coil body is preferably divided into two elements by a plane which is perpendicular to a base plane of the right cylindrical coil portion.
- 10

As mentioned above, the inductive element which can be formed with the coil form according to the invention, includes at least one coil. The coil or the coils can for example be realised by an insulated wire which is wound around the surface of the coil body in one of the coil areas provided on the surface of the coil portion by the separating plate. Such wire winding coils typically form a primary winding of the inductive element.

15

In another preferred embodiment of the invention, the at least one coil is formed by the separating plate. That is the separating plate forms a winding of the at least one coil. By providing a plurality of separating plates and connecting them in a suitable way, it is possible to provide a coil with a plurality of windings. As the number of windings of such a coil typically is smaller than the number of windings of a wired coil, the plate winding coil typically is a secondary winding of the inductive element, leading a higher current than the primary wire winding.

20

If a separating plate is used as a winding, the separating plate has two terminal projections, that are positioned preferably in near the slit. These terminal projections are for example built such that the separating plate or the separating plates can be easily connected to a printed circuit board. The circuit board includes corresponding holes or slits where the terminal projections can be inserted and for example bonded to by solder.

25

An inductive element according to the invention is manufactured by utilising a coil form according to the invention as described above. A magnetic core is inserted into the hollow coil body of the coil form and the separating plate is pushed over the coil body. At least one coil is provided on the outer surface of the coil body.

- 5 Although one metal separating plate would be sufficient to provide an inductive element according to the invention, in some applications, the inductive element advantageously includes a plurality of metal separating plates. This can be done for example to increase the number of coil areas or, where the separating plates form a winding of a coil, to increase the number of windings of such a coil.
- 10 In order to increase the number of windings of a plate winding coil, two or more separating plates can be provided directly one after the other without forming any coil areas between two adjacent plates. To prevent short circuits between two adjacent separating plates, an isolation plate (electrical isolation) is provided between two adjacent separating plates. The shape of such an isolation plate corresponds to the shape of the separating plates. As
- 15 an isolation plate does not conduct electrical current, there is no slit necessary in an isolation plate.

As already mentioned before, in some applications it is useful to realise some or all of the necessary coil windings by one or more separating plates instead of realising some or all of the necessary coils by wire windings.

- 20 The coil form according to the invention is suited to implement many different types of inductive elements like for example different types of transformers, inductors or chokes for usage in many different applications. It is also possible to utilise magnetic cores with different shapes such as for example E, U or I-shaped cores.

- 25 A widely used core type has a double rectangular shape, that is a core with two rectangular portions that have a common edge. To manufacture an inductive element according to the invention, the utilisation of such double rectangular core is preferred and where the common edge of the core is inserted into the hollow coil body.

To build such a double rectangular core, an E-shaped and an I-shaped part could be used and the middle leg of the E-shaped part is inserted into the coil body. Advantageously it can also be built from two E-shaped core halves where the middle leg of each core half is inserted into the coil body from one side of the coil body respectively.

- 5 Coil bodies which comprise two or more elements that can be fitted together by corresponding fitting means, can also be used without metal separating plates. That is they can be used in coil forms, where the separating plates are not made of metal but made of plastic.

- 10 In such coil forms, the coil body and the separating plate can build up one single piece or the separating plates can, according to another embodiment, form an additional part of the coil form. They can form for example a hollow outer coil body which can be fitted over the (inner) coil body. The separating plate can be fitted over the outer coil body to provide the coil areas. The advantage of such a configuration is, that different kinds of outer coil bodies can be pre-manufactured and fitted over the (inner) coil body to realise different kinds of coil forms with a single (inner) coil body.
- 15

From the following detailed description and from the entirety of the claims it will be clear to a person skilled in the art, that there are more advantageous embodiments and feature combinations of the invention.

Short description of the drawings

- 20 The drawings used for illustration of the examples show:

Fig. 1 A coil form according to the invention in a perspective view;

Fig. 2 a transformer body with the coil form shown in fig. 1 in a perspective, exploded view;

- Fig. 3 the assembled transformer from fig. 2;
- Fig. 4 the coil form as shown in fig. 1 in a side view;
- Fig. 5 the coil form as shown in fig. 3 assembled and with wire windings;
- Fig. 6 a further transformer body in an exploded perspective view;
- 5 Fig. 7 a separation plate of the transformer of fig. 6;
- Fig. 8 the coil form of fig. 6 with assembled separating plates;
- Fig. 9 a divided coil body according to the invention in an exploded view;
- Fig. 10 the assembled divided coil body from fig. 8.

In general, the same objects in different drawings are given the same reference numerals.

10 Ways of carrying out the invention

Fig. 1 shows a perspective view of the coil form 1 according to the invention. The coil form 1 includes a coil body 2 and a separating plate 3. The separating plate 3 is for example made of copper or aluminium or any other metal with high heat conducting capabilities and has a thickness of about 0.3 mm to 0.5 mm. The separating plate 3 has a rectangular shape, comprises an opening 4 with a rectangular shape as well and includes a slit 5 which is directed from the outer boarder to the opening 4, thereby interrupting any conductive path around the opening 4 of the separating plate 3.

The coil body 2 comprises a coil portion 6 and a flange portion 7. The coil portion 6 has substantially the shape of a hollow right cylinder with four side walls 6.1, 6.2, 6.3, 6.4 around an opening 4.1 for insertion of a magnetic core (not shown) of a transformer. The flange portion 7 is divided into two flange parts 7.1, 7.2, where each flange part 7.1, 7.2 is

connected to one of the side walls 6.3, 6.4. On the outer surface of the side walls 6.3, 6.4 recesses 8 are provided for positioning separating plates 3 after fitting them over the coil portion 6.

On the lower side of the flange portion 7, terminals 9 are located. Due to the perspective
5 view of fig. 1, some of the terminals 9 are not visible.

In fig. 2, an exploded perspective view of a transformer body 10 with the coil form 1 is shown. Fig. 3 shows the same transformer body 10 assembled. Unlike in fig. 1, three separating plates 3 are provided. The transformer body 10 includes a magnetic core 11 which consists of two E-shaped core parts 11.1, 11.2 which include two outer legs 12 and a middle leg 13 respectively. The recesses 14 on the outer legs 12 are provided for mounting
10 clamps (not shown) to hold and press the E-shaped parts 11.1, 11.2 of the core 11 together. It is to mention that the needed wire windings have to be wound around the coil body 2 before the clamps are mounted around the transformer body 10.

To assemble the transformer body 10, the separating plates 3 are pressed over the coil
15 body 2 and then the E-shaped parts 11.1, 11.2 of the core 11 are fitted together by inserting the middle legs 13 into the opening 4.1. E-shaped part 11.1 is inserted from the front (as shown in fig. 2) and E-shaped part 11.2 is inserted into the opening 4.1 from behind. Then the transformer body is clamped together for example by mounting clamps in the recesses 14.

20 In the assembled transformer body 10, both outer separating plates 3 are directly in touch with the E-shaped parts 11.1, 11.2 of the core 11. Hence, the heat generated within the windings of the transformer can be efficiently dissipated via the separating plates 3 to the core 11, which functions as a heat sink.

Fig. 4 shows the coil body 2 with three separating plates 3 in a side view. The separating
25 plates 3 are not yet fitted over the coil portion 6 and no wire windings are provided on the surface of the coil portion 6. In this view, the recesses 8 for holding the separating plates 3 and the terminals 9 on the flange parts 7.1, 7.2 can be seen clearly.

Fig. 5 shows the same coil body 2 as fig. 4 but here, the three separating plates 3 are fitted over the coil portion 6 thereby dividing the surface of the coil portion 6 into three coil areas 15. In each of these coil areas 15, a wire winding 16 is provided on the surface of the coil portion 6.

- 5 When a transformer with a coil body 2 as shown in fig. 5 is in operation, the wire windings 15 generate a lot of heat. This heat is generated just near the separating plates 3 which are made of a metal such as for example copper or aluminium or any other metal with high heat conducting capabilities. This means that the separating plates not only serve as a side support for the wire windings 15 but also dissipate the heat generated within the wire
- 10 windings 15 efficiently. As mentioned above, the separating plates 3, or at least some of them, are in direct contact with the core 11 which helps to dissipate even more heat.

At this point, it is to mention, that fig. 5 shows a small space between the outermost separating plates 3 and the flange portion 7 and the other side of the coil body 2. However, as the separating plates 3 are in direct contact with the flange portion 7 (and with the smaller

15 flange portion on the other side), there are no such spaces. This is also true for other figures, such as for example fig. 8, where there seems to be a small space between the separating plates 3.1 and the insulation plates 19.

Fig. 6 shows an exploded perspective view of another transformer body 10.1 with a further embodiment of a coil form 1.1 according to the invention. The coil body 2.1 is almost the

20 same as the coil body 2 in the transformer body 10 of fig. 2. The only difference is, that it comprises just two recesses 8 on the surface of the coil portion 6.1.

There are four separating plates 3.1 which are arranged in two groups and which have slightly a different shape than the separating plates 3 of fig. 1 and 2. The shape of the separating plates 3.1 is shown in more detail in fig. 7. The separating plates 3.1 have a

25 recess 17 on the lower edge of the opening 4 and on both sides of the slit 5.1 they have a terminal projection 18. At this point it is to say that, although all of the four separating plates 3.1 have the same shape, two of them (that is one in each group as shown in fig. 6) are laterally reversed.

As already mentioned, the separating plates 3.1 are arranged in two groups, where each group includes two separating plates 3.1, one of them being laterally reversed. To prevent current flow from one separating plate to another within a group, an insulation plate 19 is provided between the two separating plates 3.1 of one group.

- 5 The terminal projections 18 can be used to connect the separating plates 3.1 to a printed circuit board (not shown) with corresponding holes or slits where the terminal projections 18 can be inserted and for example bonded to by solder. Then, the separating plates 3.1 can be interconnected in the desired manner by traces on the printed circuit board to form the necessary windings.
- 10 Fig. 8 shows the coil body 2.1 of fig. 6 in a side view. On the outer surface of the coil portion 6.1 two recesses 8 are provided where the two plate groups, each group including two separating plates 3.1 and an insulation plate 19 between them, are positioned. The plate groups divide the outer surface of the coil body 2.1 into two coil areas 15.1.

- 15 Within the coil areas 15.1 two wire windings (not shown) can be provided in a similar way as shown in fig. 5. These wire windings could for example form one (or more) primary windings of a transformer, while the separating plates 3.1 form one (or more) secondary windings of the transformer. For this purpose, the terminal projections 18 of the separating plates 3.1 are electrically conductively connected such that the needed number of coils with the necessary number of turns in the correct direction results. In this case, where the
- 20 separating plates 3.1 are utilised as a coil of the inductive element, they have not only to be made of a good heat conducting material, but the material has also to be a good electrical conductor. Hence, it is preferred to make the separating plates of copper or aluminium or any other metal with high heat and electrical current conducting capabilities.

- 25 Fig. 9 and 10 show a coil body 2.2 which is very similar to the coil body 2 of fig. 1. The difference is, that the coil body 2.2 is divided into two elements 20.1, 20.2. Fig. 9 shows the assembled coil body 2.2 where the two elements 20.1, 20.2 are fitted together and fig. 10 shows the coil body 2.2 in an exploded view.

The coil body 2.2 is divided along a plane which is parallel to the planes of the side walls 6.3 and 6.4 and divides each of the side walls 6.1, 6.2 in two side wall sections 6.11, 6.12 and 6.21, 6.22 respectively.

5 To fit the elements 20.1, 20.2 together, there is a recess 21 provided on the front edge of side wall sections 6.12 and 6.21 and a corresponding projection 22 is provided on the front edge of side wall sections 6.11 and 6.22.

10 To summarise it can be stated that the invention teaches a coil form which enables the forming of inductive elements which can for example be manufactured very low and flat. Furthermore, an efficient heat dissipation can be achieved thanks to the metallic separating plates which are positioned directly adjacent the heat source.

Claims

1. A coil form (1, 1.1) for forming an inductive element with a core (11.1, 11.2) and at least one coil, including
 - a) a hollow coil body (2) for insertion of the core, the coil body having an outer surface for holding the at least one coil (16) and
 - b) at least one separating plate (3, 3.1) which surrounds the outer surface of the coil body thereby dividing the surface into at least one coil area (15, 15.1), characterised in that
 - c) the coil body is made of plastic and
 - d) the separating plate is made of metal, having an opening (4) for pushing the separating plate over the coil body and having a slit (5) for prohibiting leakage currents within the separating plate.
2. A coil form according to claim 1, characterised in that the coil body includes a coil portion (6) of a kind of a hollow cylinder for slipping over the separating plate and a flange portion (7) on an end region of the coil portion.
3. A coil form according to claim 2, characterised in that the coil portion includes a recess (8) for positioning of the separating plate and in that the flange portion includes a plurality of terminals (9) where at least one terminal is electrically conductively connectable to an end of one of the at least two coils.
4. A coil form according to any of claims 1 to 3, characterised in that a shape of the opening (4) of the separating plate substantially corresponds to a shape of the outer surface of the coil body and in that an internal diameter of the separating plate is smaller than an outer diameter of the coil body.

5. A coil form according to any of claims 1 to 4, characterised in that the coil body comprises at least two elements (20.1, 20.2) with means (21, 22) to fit the elements together to form the coil body.
- 5 6. A coil form according to claim 5, characterised in that the coil body comprises a first and a second element (20.1, 20.2) and in that the means to fit the elements together include a recess (21) on the first element and a corresponding projection (22) on the second element.
- 10 7. A coil form according to any of claims 5 to 6, characterised in that the coil portion is of a kind of a right cylinder, where the coil body is separated into two elements by a plane being perpendicular to a base plane of the right cylindrical coil portion.
8. A coil form according to any of claims 1 to 7, characterised in that the separating plate forms a winding of one of the at least two coils.
- 15 9. An inductive element with a coil form according to any of claims 1 to 8, a core (11.1, 11.2) inserted into the hollow coil body and at least one coil, provided on the outer surface of the coil body.
10. An inductive element according to claim 9, characterised in that it includes a plurality of separating plates (3, 3.1), where preferably an isolation plate (19) is provided between two adjacent separating plates.
- 20 11. An inductive element according to any of claims 9 to 10, characterised in that at least one winding of the at least one coil is formed by the separating plate.
12. An inductive element according to any of claims 9 to 11, characterised in that the core (11.1, 11.2) of the inductive element has a shape of two rectangular portions

with a common edge (13), where the common edge is inserted into the hollow coil body and whereby the core preferably includes two E-shaped parts (11.1, 11.2).

- 5 13. A coil form having a hollow coil body for insertion of a core of an inductive element and having an outer surface for holding a coil of the inductive element, characterised in that the coil body includes at least two elements (20.1, 20.2) with means (21, 22) to fit the elements together to form the coil body.
- 10 14. A coil form according to claim 13, characterised in that the coil body includes a first and a second element (20.1, 20.2) and in that the means to fit the elements together include a recess (21) on the first element and a corresponding projection (22) on the second element.
- 15 15. A coil form according to any of claims 13 to 14, characterised in that the coil body includes a flange portion (7) and a coil portion (6) which is of a kind of a right cylinder, where the coil body (2) is separated into two elements (20.1, 20.2) by a plane being perpendicular to a base plane of the right cylindrical coil portion.
16. A coil form according to any of claims 13 to 15, characterised in that it includes an additional hollow outer coil body for insertion of the coil body and for pushing over the separating plate.

Abstract

A coil form for forming an inductive element (10) includes a coil body (2) and at least one, for example three separating plates (3). The coil body (2) has an opening (4.1) and includes two portions, a coil portion (6) and a flange portion (7). To put the inductive element (10) together, the separating plates (3) are pushed over the coil portion (6) of the coil body (2). For positioning of the separating plates (3), recesses (8) are provided on the surface of the coil portion (6). The separating plates (3) divide the surface of the coil portion (2) into a plurality of coil areas where the coil or the coils of the inductive component (10) can be provided, for example by winding an isolated wire around the coil portion (6) in a coil area. Afterwards, the core of the inductive component is installed by fitting the two E-shaped core parts (11.1, 11.2) together such that the middle leg (13) of each core part (11.1, 11.2) is inserted into the opening (4.1) of the core body (2).

(Fig. 2)

Seite 1/3




Fig. 1

Fig. 2




Fig. 4





Fig. 5




Fig. 3




Fig. 6




Fig. 7




Fig. 8




Fig. 9




Fig. 10